

SAYBROOK LANE (EDINGER TO HEIL) CC-1690

PROJECT BID SCHEDULE

Bid No.	Const No.	Description	Contract Quantity	Unit	Unit Price	Extended Amount
1	--	MOBILIZATION	1	LS	\$ _____	\$ _____
2	--	TRAFFIC CONTROL PLAN	1	LS	\$ _____	\$ _____
3	--	FURNISH PROJECT TRAFFIC CONTROL	1	LS	\$ _____	\$ _____
4	--	FURNISH AND INSTALL SIGNING AND STRIPING	1	LS	\$ _____	\$ _____
5	--	PROJECT SPECIFIC WPCP (WATER POLLUTION CONTROL PLAN) TO ADDRESS CONSTRUCTION BMP'S.	1	LS	\$ _____	\$ _____
6	--	INSTALL AND MAINTAIN CONSTRUCTION BMP'S PER APPROVED WPCP.	1	LS	\$ _____	\$ _____
7	2	REMOVE TREE AND ROOTS; GRIND TREE STUMP AND ROOTS TO 24" BELOW TOP OF SIDEWALK/GRADE. PULL OUT ALL ROOTS WITHIN PROPOSED IMPROVEMENTS.	23	EA	\$ _____	\$ _____
8	3	REMOVE STUMP AND ROOTS (NO TREE, ONLY STUMP AT THIS LOCATION); GRIND TREE STUMP AND ROOTS TO 24" BELOW TOP OF SIDEWALK/GRADE. PULL OUT ALL ROOTS WITHIN PROPOSED IMPROVEMENTS.	2	EA	\$ _____	\$ _____
9	4	FURNISH AND PLANT NEW 24" BOX TREE, KING PALM - ARCHONTOPHOENIX ALEXANDRAE, PER HB STD. PLANS 714, 715, 716, 718 & 719 AS SHOWN ON PLANS. (ITEM INCLUDES EXISTING LANDSCAPE AND IRRIGATION REMOVAL TO ACCOMMODATE NEW TREE; REPLACEMENT OF IRRIGATION IN KIND, BACKFILLING WITH CLASS A TOP SOIL, AND INSTALLATION OF ARBOR-GARD OR APPROVED EQUAL AT BASE OF NEW TREE; 1 YEAR MAINTENANCE AND GAURANTEE)	25	EA	\$ _____	\$ _____

SAYBROOK LANE (EDINGER TO HEIL) CC-1690

PROJECT BID SCHEDULE

Bid No.	Const No.	Description	Contract Quantity	Unit	Unit Price	Extended Amount
10	5	SAWCUT AND REMOVE EXISTING SIDEWALK AND CONSTRUCT TREE WELL WITH SIDEWALK PER DETAIL ON SHEET 5. (ITEM INCLUDES REMOVAL OF SIDEWALK, 82 SF OF NEW SIDEWALK, NON-CHEMICAL WEED CONTROL BARRIER TO BE DUPONT LANDSCAPE MAX OR APPROVED EQUAL AND MULCH.)	25	EA	\$ _____	\$ _____
11	6	REMOVE AND RECONSTRUCT SIDEWALK PER HB STD PLAN 207.	5,525	SF	\$ _____	\$ _____
12	7	REMOVE AND RECONSTRUCT CURB AND GUTTER PER HB STD. PLAN 202 (CF= 8"). (ITEM INCLUDES CMB, SLOT PAVEMENT AND LOT DRAIN.)	980	LF	\$ _____	\$ _____
13	8	REMOVE AND RECONSTRUCT DRIVEWAY CURB AND GUTTER PER HB STD. PLAN 209 WITH #4 EPOXY DOWEL AT 12" OC. (ITEM INCLUDES ALL APPURTENANCES, DEPRESSED CURB & GUTTER, SLOT PAVE, AND ALL ITEMS NECESSARY TO COMPLETE THE WORK IN PLACE.)	53	LF	\$ _____	\$ _____
14	9	REMOVE AND RECONSTRUCT CURB ACCESS RAMP, DEPRESSED CURB, AND GUTTER PER CALTRANS STD PLAN RSP A88A FROM BCR TO ECR. (CASE SHOWN ON PLAN). (INCLUDES ALL APPURTENANCES, CURB GUTTER, DEPRESSED CURB, SIDEWALK, DOMES, RETAINING CURB, CMB, SLOT PAVEMENT, AND ALL ITEMS FROM ECR TO BCR NECESSARY TO COMPLETE THE WORK IN PLACE.)	9	EA	\$ _____	\$ _____
15	10	REMOVE AND RECONSTRUCT CONCRETE CURB AND CROSS GUTTER PER HB STD. PLAN 205. (INCLUDES CONCRETE CURB, SPANDRELS, TRANSITIONS, SLOT PAVEMENT, CMB, AND ALL ITEMS NECESSARY TO COMPLETE THE WORK IN PLACE.)	1,975	SF	\$ _____	\$ _____
16	11	COLD MILL EXISTING AC PAVEMENT TO A DEPTH OF 0.17' FROM EXISTING SURFACE.	9,560	SF	\$ _____	\$ _____
17	12	COLD MILL EXISTING AC PAVEMENT TO A MINIMUM DEPTH OF 0' AND TAPER FROM 0' TO 0.17' PER DETAILS ON SHEET 5.	74,300	SF	\$ _____	\$ _____

SAYBROOK LANE (EDINGER TO HEIL) CC-1690

PROJECT BID SCHEDULE

Bid No.	Const No.	Description	Contract Quantity	Unit	Unit Price	Extended Amount
18	13	CONSTRUCT A 0.17' ASPHALT RUBBER HOT MIX (ARHM-GG-C PG 64-16) WET PROCESS OVERLAY.	2,275	TN	\$ _____	\$ _____
19	14	REMOVE EXISTING AC PAVEMENT AND AB TO A DEPTH OF 0.67' AFTER COLD MILL. CONSTRUCT NEW 0.67' B-PG 70-10 AC DEEP LIFT OVER 95% COMPACTED SUBGRADE PRIOR TO PLACING 0.17' ARHM PER PLANS AND DETAIL ON SHEET 5.	3,090	TN	\$ _____	\$ _____
20	15	REPLACE WATER VALVE BOX ASSEMBLY AND ADJUST TO GRADE PER HB STD PLAN 612.	8	EA	\$ _____	\$ _____
21	16	FURNISH AND INSTALL COMPOSITE SEWER MANHOLE FRAME AND COMPOSITE COVER AND ADJUST TO GRADE PER HB STD.PLAN 513(b).	5	EA	\$ _____	\$ _____
22	18	REMOVE EXISTING, FURNISH AND INSTALL NEW TRAFFIC PULL BOX PER CALTRANS STD. ES-8 & HB STD. PLAN 422 AND ADJUST TO GRADE. PULL BOXES W/FIBERLYTE LID SHALL BE "CHRISTY FIBERLYTE" OR CITY APPROVED EQUAL. SIZE PER PLAN. LOCATION IS TO BE DETERMINED BY ENGINEER.	5	EA	\$ _____	\$ _____
23	19	ADJUST EXISTING SURVEY MONUMENT WELL TO FINISHED GRADE. PROTECT EXISTING SURVEY MONUMENT IN PLACE.	2	EA	\$ _____	\$ _____
24	20	REMOVE EXISTING, FURNISH AND INSTALL NEW WATER METER BOX PER HB STD. PLAN 601/603 AND GRADE. PULL BOXES W/ FIBERLYTE LID SHALL BE "CHRISTY FIBERLYTE" OR CITY APPROVED EQUAL.	1	EA	\$ _____	\$ _____

Total Amount Bid in Figures: \$